

RFP# 20-21-05
IGCC Building #5 (Chapel) Roof Replacement

Addendum No. 1

Project Name: IGCC Building #5 (Chapel) Roof Replacement	Project No.: RFP# 20-21-05
Prepared By: Aaron Lewis	Date: August 26, 2020

General Questions, Clarifications & Requirements:

Q: The slope of the shed roof over the basement entrance is too low for architectural shingles. What will you specify in place of architectural shingles?

A: The shed roof over the basement entrance should be covered in Certainteed XT 30 IR 3 tab shingles, color Black, to manufacturer's specification with ice and water shield underlayment.



End of Addendum #1