

To: All Interested Bidders
From: Victor Long
RE: 2010 Crooked Creek Road Stream Enhancement Project, Addendum #1
Date: May 29, 2019

The following items clarify, add to, delete from and/or otherwise change and supersede information previously issued to you in the Bid Documents for the above-referenced project. As such, said items shall be considered part of the contract and receipt of this addendum shall be acknowledged appropriately in the bid package. Please review the following items carefully and adjust your proposal accordingly.

Pre-bid Minutes and Clarifications

1. The slope of the stream shall be graded at a minimum of 2:1 slope.
2. The Contractor shall begin onsite work on or before 30 calendar days from the notice to proceed of the contract and shall notify the City in writing a minimum of 7 calendar days in advance of the date on which the Contractor intends to begin work. The Contractor shall diligently pursue the work to completion within 30 calendar days from beginning work. Voluntary shutdown or slowing of operations by the Contractor shall not relieve the Contractor of the responsibility to complete the work within the time specified in the contract.
3. It was confirmed at the pre-bid that a performance bond and a payment bond will be required
4. There will be 240 live plants in addition to the seeding and mulching for stabilization of the slope. The contractor will need to submit a list of plants suitable for live planting in the coastal plains region. The city would like to see at least 5 different varieties for plant diversity.
5. All disturbed areas will be seeded and mulched with a NCDOT approved seed and mulch for the season and application will be per NCDOT standards and specifications. The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. March 1 - December 31: 50# Tall Fescue, 10# Centipede, 25# Bermuda (hulled), 500# Fertilizer, 4000# Limestone. The seeded and mulched area will be approximately .5 acres.
6. Access to the site will be through a temporary construction easement provided by the property owner on the Crooked Creek Road side of the stream. This easement will show any trees and plants that will need to be protected. The easement will also provide a clear path for access to the project.
7. The Contractor will need to use the bid form attached to this addendum showing the new line item, Remove and replace chain link fence. The payment will be in linear feet and shall be for all the labor, materials and accessories required to complete the removal and installation.
8. For line item # 5 Channel Grading, the contract will have to move approximately 250 cubic yards of material.

9. The contractor that is awarded the contract will be provided a stream profile at the start of construction showing the new profile
10. The estimated start date of the project is negotiable, but the contract needs to be signed by the winning bidder before the end of June 2019 to allocate funds this fiscal year.
11. The erosion control matting for the project shall be at minimum a 700 gram coir matting.
12. To answer a question from a perspective bidder that did not attend the pre bid meeting. The pre bid was not mandatory, but there was an on-site meeting to discuss the projects scope. If any perspective bidder has specific questions before the bid opening they can contact me directly by phone.

Requests for additional information:

Any questions regarding this Addendum should be directed to Mr. Victor Long, at 252-329-4888 or email at vlong@greenvillenc.gov.

City of Greenville Contract Bid Form					
CROOKED CREEK ROAD STREAM ENHANCEMENT PROJECT					
ITEM	Description	Quantity	Unit	Unit Price	Total Unit Bid
1	MOBILIZATION (MAXIMUM 3%)	1	LS		
2	TREE PROTECTION	5	EA		
3	TREE REMOVAL	5	EA		
4	LIVE PLANTINGS	1	LS		
5	CHANNEL GRADING	250	LF		
6	CLASS B RIP-RAP	50	TN		
7	EROSION CONTROL	1	LS		
8	STANDARD 24" CURB & GUTTER	20	LF		
9	REMOVE AND REPLACE WOOD FENCE	60	LF		
10	REMOVE AND REPLACE CHAIN LINK FENCE	100	LF		
	Total Base Bid				

ACKNOWLEDGEMENT of reading and understanding E-VERIFY: _____

ACKNOWLEDGE OF RECEIPT OF ADDEMDUM NO. 1 _____

Contractor _____

License No. _____

Contact Name. _____

Contact Telephone No. _____

Address for Giving Notices. _____

Date _____