

STREET LISTING/ESTIMATES FOR ASPHALT AND MILLING – BASE BID

***Streets marked by asterisk will be milled with 4' Edge Milling**

Street Name	From	To	Milling (SY)	Estimated 4" Base Repair (Tons)**	Resurfacing (Tons)	Thickness (inches)
<i>Mall Dr.</i>	<i>SW Greenville Blvd.</i>	<i>S. Memorial Dr.</i>	<i>9,488</i>	<i>150</i>	<i>1,050</i>	<i>2</i>
<i>Cotanche St.</i>	<i>E. 10th St.</i>	<i>Reade Cl.</i>	<i>6,600</i>	<i>60</i>	<i>728</i>	<i>2</i>
<i>E. 7th St.</i>	<i>Cotanche St.</i>	<i>End City Maintenance</i>	<i>1,203</i>	<i>40</i>	<i>270</i>	<i>2</i>
<i>Sherwood Dr.</i>	<i>Red Banks Rd.</i>	<i>Street End</i>	<i>4,750</i>	<i>80</i>	<i>1,050</i>	<i>2</i>
<i>E. 14th St.</i>	<i>Charles Blvd.</i>	<i>Cotanche St.</i>	<i>3,680</i>	<i>20</i>	<i>820</i>	<i>2</i>
<i>Landmark St.</i>	<i>SW Greenville Blvd.</i>	<i>E. Baywood Ln.</i>	<i>11,568</i>	<i>100</i>	<i>1280</i>	<i>2</i>
<i>Spring Forest Rd.</i>	<i>RxR Crossing</i>	<i>John Hopkins Dr.</i>	<i>5,000</i>	<i>120</i>	<i>550</i>	<i>2</i>
<i>Gabriel Dr.</i>	<i>Spring Forest Rd.</i>	<i>Pavement Joint</i>	<i>770</i>	<i>20</i>	<i>90</i>	<i>2</i>
<i>Stanwood Dr.</i>	<i>Chowan Rd.</i>	<i>Wesley Rd.</i>	<i>3,650</i>	<i>100</i>	<i>410</i>	<i>2</i>

W. Moore St.	N. Memorial Dr.	Melody Ln.	6,650	120	740	2
Golf Club Wynd.	End City Maintenance	NC 43	6,006	60	1,330	2
S. Baywood Ln.	Woodhaven Rd.	Cedarhurst Rd.	3,240	120	720	2

CONCRETE CURB RAMPS WILL BE SHOWN ON MAPS IN APPENDIX B

STREET LISTING FOR MICRO PAVING – BASE BID

Street Name	From	To
*LANGSTON BLVD.	THOMAS LANGSTON RD.	STREET END
GOLDEN RD.	CEDAR LN.	SE GREENVILLE BLVD.
PALMER CT.	WYNGATE DR.	STREET END
*SATTERFIELD DR.	WYNGATE DR.	WYNGATE DR.
ST. CHARLES CL.	STREET END	SATTERFIELD DR.
*WYNGATE DR.	MACGREGOR DOWNS RD.	STREET END
ADAMS BLVD.	SE GREENVILLE BLVD.	BLOOMSBURY RD.
S. ELM ST.	E. 14 TH ST.	SE GREENVILLE BLVD.
W. 1 ST .	N. PITT ST.	S. WASHINGTON ST.
*E. 4 TH ST.	FOREST HILL CL.	HICKORY ST.
MARTINSBOROUGH RD.	EVANS ST.	GRANVILLE DR.

*Roadway will have 4" Base Patching

CRACK SEALING STREET LIST – BASE BID

Street Name	From	To
*DALEBROOK CL.	E. 14 ST.	DEERWOOD DR.
*DEERWOOD DR.	DALEBROOK CL.	KINGSBROOK RD.
*E. 4 TH ST.	HICKORY ST.	LAUREL ST.
*E. 5 TH ST.	TRUSTEES WY	E. 10 TH ST.
*KINGSBROOK RD.	E. 14 TH ST.	CUL-DE-SAC
OXFORD RD.	E. 10 TH ST.	YORK RD.
*RED BANKS RD.	EVANS ST.	SE GREENVILLE BLVD.
*RED BANKS RD.	E. ARLINGTON BLVD.	CHARLES BLVD.
*REGENCY BLVD.	S. MEMORIAL DR.	EVANS ST.
*S. ELM ST.	E. 10 TH ST.	E. 14 TH ST.

*Seal Cracks at Edge of Pavement/Gutter Joint

GAS VALVE LOCATIONS

- 1) E 14th St. and Glen Arthur one valve in intersection
- 2) W Moore St. and Legion St. one valve in intersection
- 3) W Moore St. and Taylor St. one valve in intersection (possibly already paved over will require additional investigation)

These valves will be adjusted by the Contractor, and use of rings for adjustment will be allowed on these valves only.